BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No. 21

Name of the Work : Providing chain link fenceing for the Sy no. 15 at CQAL main road (lions road) in ward no. 08 in kodigehalli sub division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	27.70	**KSRB 2-2.1 :** Earthwork excavation for foundation of building, water supply sanitary lines and electrical conduits either in pits or in trenches 1.5m in depth including dressing the bottom and sides of pits and trenches stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as pwe specifications. specification No. KBS 2.1 (b)/2.3.5 (P.6/1.2.4 PWD SR 2010-11)	Cum	127.20	
2	6.93	**KSRRB 2900-4.1:** Providing and laying in position plain **cement concrete mix 1:4:8** with stone aggregate 40mm and down size in foundation upto a depth of 2m below ground level and upto a height of 1.5m above ground level / bed level machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification No. 1000, 1700 MORT & H Specification No. 1000 / 1700 MOST Specification No. 1000 / 1700 **(Page No. 204 & Item No. 35.15)**	Cum	3287.06	
3	20.78	**KSRB 4-1.5 :** Providing and laying in position **plain cement concrete of nominal mix 1:2:4** using **20 mm** and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms, thick, well compacted, in foundation, plinth, including cost of all materials, labour, **HOM** of machinery, curing complete as per Spefication. Specification No. KBS 4.1, 4.2 **(Page No. 12 & Item No. 4.1).**	Cum	4306.78	
4	524.40	Supplying and fixing **M. S. Rectangular Poles** made but of 2 equal angles of 65 x 65 x 6 mm welded together and fixed inCC (1:2:4) with 2 Nos. 16 mm dia M. S. hold fast rods each of length 25 cms, including cost of all materials, cutting, bending scafolding wherever necessary, nicely finishing the welded joints with all lead and lift and as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earth work and concrete) **(Page No. 232 & Item No. 37.2).**	M	742.00	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
5	819.00	Providing **Chain Link Fencing** 50 mm size of 8 guage property striched between rectangular poles and fixed with suitable bolts and nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required, including cost of all materials, labour, lead and lifts, cutting, bending scafolding wherever necessary, wastage and lapping etc., complete as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting **(Page No. 232 & Item No. 37.3).**	Sqm	558.62	
6	1092.00	Providing and fixing **M. S. Block Pope** of 38 mm dia, of heavy guage of 1:4, including removing the bends, cutting the pipe in between the two verticle poles (M. S. Rectangular Poles) and spot welding the chain link with M. S. Block Pipe, including cost of all materials, wastage in cutting and scaffolding wherever necessary, with all lead and lift as directed by the Engineer-in-charge of the work etc., complete including 2 coats of approved quality paint over one coat of shop painting **(Page No. 232 & Item No. 37.4).**	Sqm	257.58	
7	27.70	Lead for disposal of debris shall be payable at garage rates by Mechanical means inlcuding loading and unloading for 6 Kms (Page No. 132/Item No. Note:1) Conveyiing	Cum	82.68	

Signture of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ .....(Nil
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-92